


MANHOLE REGRADING DETAIL



VALVE BOX REGRADING DETAIL

GENERAL NOTES:

1. ADJUSTMENT TO GRADE OF FRAME AND COVER SHALL BE MADE BY VARYING BRICK COURSES DIRECTLY UNDER FRAME, USING FOUR COURSE MAX. IF LESS THAN ONE COURSE IS REQUIRED, GROUT ONLY SHALL BE USED. IF ADJUSTMENT WOULD REQUIRE GREATER THAN FOUR COURSES, THE CONE SHALL BE REMOVED, BARREL HEIGHT ADJUSTED AND CONE REPLACED. ADJUSTMENT RINGS MAY BE USED FOR MINOR ADJUSTMENT REQUIREMENTS.
2. FOR SMALL ADJUSTMENTS WATER VALVE EXTENSION COLLAR & INSERT MAY BE USED. SEE DWG. 2332.

CONSTRUCTION NOTES:

- A. FOUR BRICK COURSES MAX.
- B. OVERLAY.
- C. USE A CONC. PAD 5' X 5' IN ALL AREAS.
- D. M.H. FRAME & COVER.
- E. STD. PAVING SECT.
- F. 1/2" PLASTER INSIDE & OUTSIDE EXCEPT ON PRE-CAST UNITS.
- G. A.T.B. OR C.T.B.
- H. SUBGRADE.
- J. SEWER LINE.
- K. NEW PORTLAND CEMENT CONC.
- L. NEW PAVING MATERIAL.
- M. EXIST. PAVEMENT.
- N. CUT LINE.
- P. EXIST. CONC.
- Q. VALVE BOX EXTENSION, SEE DWG. 2325.

REVISIONS	CITY OF ALBUQUERQUE	
	PAVING	
	MH & VALVE BOX REGRADING	
	DWG. 2460	
		AUG. 1966